

7-7 15-065-02656-00-00

6 031130

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1958.  
NE NE, NE SEC. 5, T 8 S, R 24 W/E  
4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5447

Lease Name Nana NW Well # Unit 303  
County Graham 126.75  
Well Total Depth 3900 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 226'

Operator: Oxy USA Inc.  
Name & Address 3545 NW 58th St  
Oklahoma City, Ok. 73112

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A   
Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number  
Address Russell, Ks.

Company to plug at: Hour: AM Day: 7 Month: July Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 226' w/165 sks cwc. 5 1/2" set at 3900' w/125 sks.

PBTD 3710' Perf at 3731' - 3862'. Shot at 2050' Anhy 1200' below Dakota. Order 300 sks  
Cement Blend w/600# Hulls. Allied Cement Co. Wellbrock Hensley LaRue Water Trucks.

RECEIVED  
STATE CORPORATION COMMISSION  
9-16-1988  
SEP 16 1988

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:30AM Day: 7 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/250 sks Cement Blend w/500# Hulls.

Mixed in to max Psi 300#. Close in Psi 150#. Squeezed annulus w/50 sks Cement Blend w/100#  
Hulls to maz Psi 200#. Close in 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-20-88

INV. NO. 22314

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

D