

7-7 15-065-03100-00-00

6 031131

API NUMBER 15- 1959

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N/2SE NE, SEC. 5, T 8 S, R 24 W/E
3630 feet from S section line
660 feet from E section line

RECEIVED
STATE CORPORATION COMMISSION
9-16-1988
SEP 16 1988
CONSERVATION DIVISION
Wichita Kansas

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: Oxy USA Inc.
Name & Address: 3545 NW 58th St.
Oklahoma City, Ok. 73112

Lease Name Nana NW Well # Unit 305
County Graham 125.61
Well Total Depth 3865' feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number
Address Russell, Ks.

Company to plug at: Hour: PM Day: 7 Month: July Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 221' w/165 sks cwc. 5 1/2" set at 3865' w/125 sks.

Perfs 3698' - 3826'. Shots at 2050' Anhy. 1200' below Dakota. Order 300 sks cement

Blend w/600# Hulls. Allied Cement Co. Wellbrock Larue Hensley Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 7 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/200 sks Cement Blend w/500# Hulls.

To max Psi 1000#. Close in Psi 500#. Plug complete. Squeezed 8 5/8" w/50 sks Cement Blend w/100# Hulls to max Psi 400# Close in Psi 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 9-20-88
INV. NO. 22316

Signed Carl Goodrow (TECHNICIAN)