

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22800-00-00  
Spot: SENENE Sec/Twnshp/Rge: 5-8S-24W  
990 feet from N Section Line, 330 feet from E Section Line  
Lease/Unit Name: TEEL Well Number: 1  
County: GRAHAM Total Vertical Depth: 3895 feet

Operator License No.: 9449  
Op Name: GREAT EASTERN ENERGY & DEV. CO  
Address: 550 W. TEXAS STE 660  
MIDLAND, TX 79702

Production Casing Size: 5.5 feet: 3892 175 SX CMT  
Surface Casing Size: 8.625 feet: 202 165 SX CMT

\$126.59

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/29/2003 11:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: GREAT EASTERN ENERGY Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2537

Proposed Plugging Method: Ordered out 235 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perfs 3834'-3840' and 3853'-3859'.  
PBTD 3873'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/29/2003 4:00 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Sanded back to 3750' with 5 sxs cement on top.  
Shot casing at 2120' - worked - parted 80' down.  
Screwed back into casing.  
Allied pumped 145 sxs 60/40 pozmix - 10% gel with 300# hulls. Displaced to 1280'.  
S.I.P. 500#. One hour. Bled off.  
Shot pipe off at 1250'.  
Allied pumped 40 sxs cement with 200# hulls.  
Pulled to 150'. Allied pumped 30 sxs cwc.  
PTOH. Topped off with 20 sxs cement.

RECEIVED  
5-5-2003  
MAY 05 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-6-03

INV. NO. 2003061496

MAY 01 2003

GREAT EASTERN ENERGY & DEVEL  
MIDLAND TX 79702

5-08S-24W  
SE NE NE

#1 TEEL

site 2-1/2 N & 2 W OF PENOKEE KS

cty: GRAHAM

API 15-065-22800

contr: VONFELDT DRILLING #1

field: NANA NW

geol:

fr  
date 10/05/2000

spc  
date 12/16/2000

drilg  
comp 12/22/2000

card  
issued 05/14/2001

last  
revised 05/14/2001


ELV: 2395 GL  
tops.....depth/datum  
ERTD .....3950 -1555  
NO TOPS RPTD

0

**IP status**

OIL, P 10 BO & 1 BWPD, LKC, INTV NA, 03/15/2001

CSG: SP 220 (ALT 2), PROD CSG NA

COMMENT: MI & RURT 12/15/2000

TRGT ZN: LKC (OIL), PTD 3950 (PENN), MICT - CO, PF  
(LKC) INTV NA, AC'D, GSO, POP, IPP 10 BO & 1 BWPD,  
3/15/2001 - TIGHT HOLE - NO OTHER INFO AVAILABLE -  
TEMP COMP 5/14/2001

COPYRIGHT 2001  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

R