

10-15-87

6 030979

API NUMBER 15- 065-21,156-00-01

NE NE NESEC. 6, T 8 S, R 24 W/E

4950 feet from S section line

330 feet from E section line

Lease Name Teel Well # 1-6 SWD <sup>KCC</sup> ZAP

County Graham 128.70

Well Total Depth 3960 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well Gas Well Input Well <sup>KCC</sup> X ZAP SWD Well ~~X~~ D&A

Docket No. E-23,144

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 15 Month: Oct. Year: 19 87

Plugging proposal received from Ronnie

(company name) Kelso Casing (phone)

were: 8 5/8" set at 276' w/220 sks 4 1/2" set at 3959' w/100 sks PBTD 3930'.

Perfs 3855' - 3917'. 4 1/2" Perf at 2130' Anhy w/cement circulated to surface.

Order 140 sks ATL 65/35 Pozmix 10% Gel 2% Dical Cement Blend, Allied Cement Co.

Joe Neuman Water Truck.

Plugging Proposal Received by Carl Goodrow <sup>Carl Goodrow</sup> (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:00 AM Day: 15 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/140 sks ATL Cement Blend to Max Psi

1000# Close in PSI 800#. 8 5/8 4 1/2" casing annulus had cement to surface. Pressured

to 500#. Plug complete.

11-30-1987

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

DATE 12-4-87

INV. NO. 19105

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow