

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01334-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 3-8S-24W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: NEAL B Well Number: 1
County: GRAHAM Total Vertical Depth: 3842 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 150 100 SX CMT
Production: Size 5.5 feet: 3840 100 SX CMT 124.87
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2001 12:00 PM

Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION

Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common with sand/yard.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/02/2001 1:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 150' w/100 sxs. 4 1/2" set at 3840' w/100 sxs.
Squeezed to surface with cement in 8 5/8" annulus.
No fluid in hole - swabbed dry.
Filled casing to surface with 8 yards Redi-Mix.
Plug complete.

INVOICED
DATE 5-29-01
INV. NO. 2001061839

KANSAS CORPORATION COMMISSION
MAY 22 2001
CONSERVATION DIVISION
5/22/01

Remarks:

Plugged through: CSG

District: 04

10

Signed Carl Goodrow
(TECHNICIAN)

MAY 09 2001

BENSON-MOUNTAIN #1 NEAL 'B' 3-8-24W
 SW SW NW


Contr. BERWICK GRAHAM County

E. 2352 Comm. 1-31-54 Comp. 3-26-54 IP 1673 BOPD

Tops	Depth	Datum
ANH	2030	322
HEEB	3562	-1210
LANS	3580	-1228
B/KC	3808	-1156
TD	3842	-1190

Casing
 8" 160
 5" 3840
 PERF 3762-70: SWB 21 BOPD:
 ACID 1000: 36 BOPD

NANA POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS