

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01335-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 3-8S-24W
3300 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: NEAL B Well Number: 2
County: GRAHAM Total Vertical Depth: 3790 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 260 100 SX CMT
Production: Size 5.5 feet: 3789 100 SX CMT \$123.18
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2001 9:00 AM

Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION

Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement with sand/yard.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/02/2001 11:30 AM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 260' w/100 sxs. 4 1/2" set at 3789' w/100 sxs.
Squeezed N/A cement at surface in 8 5/8" annulus - could not pull casing.
Prod. Perfs 3726' - 3730'.
No fluid in hole.
Filled casing to surface with 8 yards Redi-Mix.
Plug complete.

INVOICED

DATE 5-29-01

INV. NO. 2001061839

KANSAS CORPORATION COMMISSION

MAY 22 2001

5/22/01
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

BEYNSON-MONTAIN

#2 NEEL 'B'

3-8-24W
E2 SW NW

Contr. _____ GRAHAM _____ County

E 2339 REComm. _____ Comp. 12-31-54 IP 234 BOPD
PHY POT

Tops	Depth	Datum
HEEB	3545	-1206
LANS	3568	-1229
B/KC	3785	-1146
TD	3790	-1151

4 1/2" casing
5" 3710
DST 3603-30 1/2 HR, 1200' GAS, 1520' OIL
60' WTRY OIL, BHP 1280#
DST 3646-60/1 HR, 550' GAS, 195' FRE
OIL, BHP 560#
DST 3742-50/1 HR, 1140 GAS 720' OIL,
BHP 320#
DST 3752-70/1 HR, 600' GAS, 60' H OCM
BHP 690#
PERF 3726-30; 3742-48: 12 3/4 BOPH:
AGID 1000: 31 1/2 BOPH
NANNA POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

