

STATE OF KANSAS
STATE CORPORATION COMMISSION
40 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-01325-00-00

API NUMBER Completion 6-14-58

LEASE NAME Bethell

WELL NUMBER "B" #1 _____

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 16 TWP. 8S RGE. 23W (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 6-17-94

Plugging Completed 6-17-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kenbill Oil Company

ADDRESS 5105 Telstar Street Great Bend, KS 67530

PHONE# (316) 564-3438 OPERATORS LICENSE NO. 6332

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3655'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	160'	none
				5 1/2	3654'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
PLUG JOB ONLY: Rod & pump stuck in tubing @ 2400'. backoff rod & tubing @ 2400'. L. K.
Wireline perforated well @ 1834' & 1030'. Ran tubing in to 2400'. Pumped 100 sx cement w/300# hulls to surface. Pulled tubing out of hole. Tied on to 5 1/2" casing & pressured up to 500#.
Tied on to 8 5/8 surface & pumped 50 sx cement. 60/40 poz 10% gel. Plugging complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kenbill Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) Wichita Office of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 94

Irene Herzberg
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1994
6/21/94

CONSERVATION DIVISION
Wichita Office