

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

Form CP-4
Rev. 12-15-80

SFP 2 1982

9/2/82

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

15-065-19089-00-00

COUNTY Graham SEC. 16 TWP. 8 RGE. 23W E/W
Location as in quarters or footage from lines:
SW NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner Kelso Casing Pulling
Lease Name Bethel #1 Well No. _____
Office Address Box 347 Chase, Kansas 67524
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 3-4-82
Plugging completed 8-20-82
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom T.D. 3675'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	171'	none
				4-1/2"	3674'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3050' and ran 5 sacks cement. Shot casing@2000',
pipe parted, no pipe recovery. ~~Mixed 4 sacks hulls with 250 sacks 50/50 pos, 6% gel,~~
~~3% cc and pumped down the 8-5/8" and shut in.~~

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1982



Irene Hoover
Notary Public.

My Commission expires: _____

15-065-19089-00-00

DRILLERS LOG
B. N. HILBURN & ATRY
1 BETHELL
SW NE NW, SEC. 16-8-23N
GRAHAM COUNTY, KANSAS

Contractor - Tom Kat, Inc.

Commenced: 9/4/64
Completed: 9/12/64
Elevation: 2183 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	110	Surface Hole	
110	171	Blue Shale	171' 8-5/8' Surf. Csg. w/135 Sacks C.C.
171	665	Blue Shale & Sand	
665	2870	Shale	
2870	2955	Shale w/Lime	
2955	3023	Lime & Shale	
3023	3150	Shale & Lime	
3150	3378	Lime & Shale	
3378	3525	Lime	
3525	3525	Kansas City	Log Tops:
3525	3528	Kansas City Lime	Heabner 3398
3528	3675	Lime	Toronto 3423
3675		Rotary Total Depth	Lansing 3441
			Base K.C. 3653
			4 1/2' Csg. 3674

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.


Richard C. Davis, Geologist

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 16th day of September, 1964.


Esther Lanning, Notary Public

My Commission Expires: Jan. 19, 1965