

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-228350000  
LEASE NAME Roger  
WELL NUMBER 1  
330 Ft. from S Section Line  
1,720 Ft. from E Section Line  
SEC. 16 TWP. 8 RGE. 23 ~~W~~  
COUNTY Graham

JUN 13 2002  
6/13/02  
Conservation Division  
Wichita, Kansas

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pioneer Resources  
ADDRESS 177 W. Limestone Road, Phillipsburg, KS 67661  
PHONE#(785) 543-5556 OPERATORS LICENSE NO. 32016

Date Well Completed 5-23-02  
Plugging Commenced 5-23-02  
Plugging Completed 5-24-02

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-23-02 (date)  
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	233'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each section.  
Push plug to 1,860', spot 25 sax cement on plug thru drill pipe. Push plug to 1,025', spot 100 sax cement on plug thru drill pipe. Push plug to 285', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184  
Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pioneer Resources

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor  
(Employee of ~~XXXXXX~~ or ~~XXXXXX~~)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P. Beeman  
(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 30th day of May, ~~XX~~ 2002

My Commission Expires: \_\_\_\_\_

Ruth Phillips  
Notary Public  
My Appt. Exp. 5-26-03




15-065-22835-00-00  
*Shields*

*Russell, Kansas*

WELL LOG

Operator: Pioneer Resources  
Well: Roger #1  
Commenced: May 17, 2002  
Completed: May 24, 2002  
Contractor: Shields Drilling Co.

Well Description: SE SW SE  
Sec. 16-8S-23W  
Graham Co., KS



CASING RECORD  
Size Run Pulled  
8 5/8" 233' Cmt'd. w/165 sax

Elevation: 2,169' KB  
Treatment:  
Production: D & A  
Tops:

RECEIVED  
JUN 0 3  
KCC WICHITA  
6/4/02

..... Figures Indicate Bottom of Formations .....

Sand & shale	1,826'	
Anhydrite	1,860'	
Sand & shale	2,175'	
Shale	3,335'	
Shale & lime	3,465'	
Lime	3,665'	RTD

Notes