


15-063-21364-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Graham County. Sec. 35 Twp. 8S Rge. 23W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
500' from N.L. 500' from E.L. of SW  
Lease Owner Suburban Propane Gas Corporation  
Lease Name Gano #1 Well No. #1  
Office Address P.O. Box 17689 San Antonio, TX. 78217  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed January 13 1981  
Application for plugging filed January 13 1981  
Application for plugging approved January 13 1981  
Plugging commenced January 13 1981  
Plugging completed January 13 1981  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4080'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

T.D. 4080'  
Set 1st Plug @ 800' with 70 sx.  
Set 2nd Plug @ 240' with 20 sx.  
Set 3rd Plug @ 40' Solid Bridge with 10 sx.  
Rathole with 5 sx. 50-50 posmix, 6% gel.

Plug was down @ 11:00 a.m., 1/12/81.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 20 1981

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc. 1-20-81


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec./Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January, 1981

My commission expires 8-18-84

Jeanette A. Metheny  
Jeanette A. Metheny Notary Public.



CONTRACTOR'S WELL LOG 15-065-21364-00-00

OPERATOR: Suburban Propane Gas Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: GANO #1  
 LOCATION: 500' from N.L. 500' from E.L. of SW  
 Section 35-8S-23W, Graham County, Kansas  
 SPUD DATE: 1/05/81  
 COMPLETION DATE: 1/12/81

0	1839	Shale & Sand
1839	1876	Anhydrite
1876	3075	Shale
3075	3711	Shale & Lime
3711	3950	Lime
3950	4080	Cong. & Churrent
	4080	Rotary Total Depth

Spud @ 6:00 p.m., 1/05/81. Drilled 251' in a 12½" hole. Ran 6 jts. of 8 5/8" - 23# casing (new) (tally 242.04'). Set @ 249' RTD. Cemented with 225 sx. of common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 10:30 p.m., 1/05/81.

4080' T.D. Set 1st Plug @ 800' with 70 sx. Sent 2nd Plug @ 240' with 20 sx., Set 3rd Plug @ 40' Solid Bridge with 10 sx., Rathole with 5 sx, 50-50 posmix, 6% gel. Plug was down @ 11:00 a.m., 1/12/81.

SAMPLE TOPS:

Anhydrite 1839'  
 B/Anhydrite 1876'

RECEIVED  
 STATE CONSERVATION DIVISION  
 JAN 20 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

1-20-81

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GANO #1, 500' from N.L. 500' from E.L. of SW, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of January, 1981.

Jeanette A. Metheny  
 Jeanette A. Metheny, Notary Public

