

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

5/26/98
 RECEIVED
 KANSAS

API NUMBER 15-065-20899-000

LEASE NAME Casey Jones

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2-2

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 36 TWP. B5 RGE. 23 or (W)

COUNTY Graham

Date Well Completed 3/18/77

Plugging Commenced 4/22/98

Plugging Completed 4/22/98

LEASE OPERATOR Eagle River Energy Corporation

ADDRESS 7060 S. Yale, Suite 609, Tulsa, OK 74136

PHONE#(918) 494-8928 OPERATORS LICENSE NO. 31070

Character of Well oil producer

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/04/98 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Lansing-Ks City Depth to Top 3717 Bottom 3753 T.D. 3830

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|----------------|------|------|-------|--------|------------|
| Topeka | lime-oil/water | 3304 | 3514 | 8 5/8 | 119' | none |
| Heebner | shale | 3514 | 3546 | 4 1/2 | 3829' | none |
| Toronto | lime-oil/water | 3546 | 3564 | | | |
| Lansing | lime-oil/water | 3564 | 3780 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.

Backhoe dig out cellar to bradenhead, L-K Wireline perf w/3 shots in Dakota at 1150, Anhydrite at 1930, welded 2" collar below bradenhead. RU Allied Cementing, 4 1/2 csg mix and pump 25 sx cement w/200# hulls, follow w/12 sx gel. Follow w/125 sx cement w/200# hulls 1000# max pressure. Shut-in press 600#. 8 5/8 csg 25 sx cement w/100#
 (If additional description is necessary, use BACK of this form.)

hulls, 300# max pressure. Shut-in pressure 150#.

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eagle River Energy Corporation

STATE OF OK COUNTY OF Tulsa, ss.

Mark P. Godsey (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Mark P. Godsey

(Address) Same as above

SUBSCRIBED AND SWORN TO before me this 13th day of May, 19 98

Dora R. Draville
 Notary Public

My Commission Expires: 8-7-2000