

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

PCW 5/24/98
API NUMBER 15-065-20295-00-03

LEASE NAME Casey Jones

WELL NUMBER 4-2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 36 TWP. 8S RGE. 23 or (W)

COUNTY Graham

Date Well Completed 9/10/76

Plugging Commenced 4/22/98

Plugging Completed 4/22/98

LEASE OPERATOR Eagle River Energy Corporation

ADDRESS 7060 S. Yale, Suite 609, Tulsa, OK 74136

PHONE# (918) 494-8928 OPERATORS LICENSE NO. 31070

Character of Well oil producer

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/04/98 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Lansing-Ks City Depth to Top 3760 Bottom 3786 T.D. 3875

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	unknown-no logs			8 5/8	217'	none
Heebner	" "			5 1/2	3865'	none
Toronto	" "					
Lansing	lime-oil/water	est 3560	est 3780'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s

Backhoe dig out cellar to bradenhead, I-K Wireline perf w/3 shots in Dakota at 1150, Anhydrite at 1930, RU Allied Cementing, 5 1/2 csg mix & pump 25 sx cement w/100# hulls, follow w/17 sx gel, follow w/175 sx cement w/300# hulls, 1500# max pressure. SI press 500#. 8 5/8 csg mix & pump 25 sx cement w/100# hulls, max press 500#, shut-in

(If additional description is necessary, use BACK of this form.)

pressure 100#.

Name of Plugging Contractor Allied Cementing License No.

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eagle River Energy Corporation

STATE OF OK COUNTY OF Tulsa, ss.

Mark P. Godsey

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Mark P. Godsey

(Address) Same as above

SUBSCRIBED AND SWORN TO before me this 13th day of May, 19 98

Dora R. Gravitte
Notary Public

My Commission Expires: 8-7-2000