

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22731-00-01 *KCC ops 2-21-08*
Spot: NESESE Sec/Twnshp/Rge: 32-27S-3E
967 feet from S Section Line, 389 feet from E Section Line
Lease Name: MORCO B Well #: 1-32
County: BUTLER Total Vertical Depth: 3090 feet

Operator License No.: 9913
Op Name: BULLSEYE PETROLEUM, INC.
Address: 15820 PLYMOUTH RD
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2511		
SURF	8.625	249		

100.43

Well Type: EOR UIC Docket No: E 25254.1 Date/Time to Plug: 09/25/2007 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: RICHARD KANE Company: RICHARD KANE Phone: (918) 214-3471

Proposed Plugging Method: SET CIBP @ 2285' AND CAP W/4 SXS CEMENT, LOAD 4-1/2" CASING AND PRESSURE TO 100# TO INSURE INTEGRITY OF CASING. PERFORATE @ 1850', AND PUMP 50 SXS 60/40 POZMIX 4%. PERFORATE @ 300', AND CIRCULATE BACKSIDE OF 4-1/2" TO SURFACE W/60/40 POZMIX 4% GEL TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/08/2007 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/CIBP AND SET @ 2260', DUMP BAILED 4 SXS CEMENT ON TOP. PRESSURED TESTED 4-1/2" CASING @ 150#, HELD OK. RIH PERFORATED 2' W/4 HOLES @ 1850', WELL WOULD NOT CIRUCLATE, RIH PERFORATED 2' W/4HOLES @ 1200'. COULD PUMP INTO 4-1/2", BUT WELL WOULD NOT CIRCULATE ON BACKSIDE. CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL. DISPLACED CEMENT PLUG W/20 BBLs FRESH WATER, RIH PERFORATED HOLES @ 300', WELL WOULD NOT CIRCULATE, SHUT DOWN. 10-8-2007, RIH TAGGED CEMENT @ 1170'. Rih W/TBG @ 300', CONSOLIDATED MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. RIH W/1" TBG ON BACK SIDE @ 30', CONSOLIDATED MIXED & PUMPED 10 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 1200 10-8-2007. CONSOLIDATED CEMENT TICKET #12758.

Perfs:

INVOICED
DATE 10/23/07
INV. NO. 2008060660

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2007
CONSERVATION DIVISION
WICHITA KS

Remarks: E-25,254, -097.11800,37.65300, PERFS 2338'-2354'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT