

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20036-00-00
Spot: NWNESW Sec/Twnshp/Rge: 11-22S-12W
2340 feet from S Section Line, 3668 feet from E Section Line
Lease Name: VOIGHT A Well #: 1
County: STAFFORD Total Vertical Depth: 3637 feet

Operator License No.: 7702
Op Name: STALCUP, RALPH DBA STALCUP OIL C
Address: 3218 MAIN ST # 7
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2256 | | |
| PROD | 5.5 | 3633 | 0 | WITH 150 SX CMT |
| SURF | 8.625 | 229 | | |

118.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2008 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RICHARD STALCUP Company: STALCUP OIL COMPANY Phone: (620) 793-3118

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2008 3:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

FOUND BRIDGE @ 2280'. SET CIBP @ 2256'. PERFORATED 5 1/2" @ 700'. RAN TBG TO 706'. PUMPED 300 SX CMT WITH 400# HULLS. HAD CIRCULATION UP 8 5/8" X 5 1/2" & 5 1/2". LOSS CIRCULATION. PULLED TBG AND SHUT DOWN FOR 4 HOURS. RAN TBG BACK TO 706' CIRCULATED CMT TO SURFACE UP 8 5/8" X 5 1/2" & 5 1/2" WITH 115 SX CMT. PULLED TBG. TOPPED OFF HOLE WITH 50 SX CMT.

Perfs:

INVOICED
DATE 2-19-08
INV. NO. 200800252

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB - 5 2008
KCC Dodge City

Signed

Richard W. Lacey

(TECHNICIAN)

Form CP-2/3

PKT