

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20211-00-00
Spot: SESESW Sec/Twnshp/Rge: 8-9S-19W
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BAYARD Well #: 3
County: ROOKS Total Vertical Depth: 3540 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3525	0	w/150 sxs cmt
SURF	8.625	206	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2008 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel spacer.
Ordered out additional 200 sxs 60/40 pozmix - 4% gel - 200# hulls.
Fluid 100' from surface.
Perforate 1900' - 1500' - 825'. No squeeze records.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2008 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated 1500' and 825' two shots per foot. Hit bridge at 1734'.
Ran tubing - worked thru bridge at 1734'. Tagged bottom at 3418'.
Allied pumped 11 sxs gel spacer - followed with 40 sxs cement with 200# hulls.
Pulled tubing to 1950' - pumped 260 sxs cement with 300# hulls - cwc.
PTOH. W.O.C.
Allied pumped 80 sxs cement with 200# hulls.
Max. P.S.I. 300#. S.I.P. 200#.
Hooked up to backside - pumped 55 sxs cement.
Max. P.S.I. 250#. S.I.P. 200#.
02/07/2008 - 5 1/2" casing topped off with 25 sxs.

Perfs:

Top	Bot	Thru	Comments
3440	3443		
3420	3424		
3403	3406		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 15 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

KATHOL PETROLEUM, INC. #3 BAYARD 8-9-19W
 WICHITA, KS. SE SE SW
 Contr. KATHOL PETROLEUM, INC. Cty. ROOKS
 Geol. JERRY JESPERSEN Pool MC CLELLAN
 E. 2063 KB Cm. 6/3/69 Cp. 7/31/69 IP PMP 64 BOPD + 7
 BWPD/LANS 3403-06

API 15-163-20,211

LOG Tops	Depth	Datum	
ANH	1477	+ 586	Csg. 8-5/8" 206/150 sx
B ANH	1517	+ 546	5 1/2" 3525/150 sx
TOP	3021	- 958	
HEEB	3226	-1163	DST 3415-46/75", 50' OCM, BHP
TOR	3248	-1185	704-152#/30", FP 48-67#
LANS	3268	-1205	TEMP 96
BKC	3472	-1409	
CONG	3500	-1437	CO TO 3532, DD TO 3540 TD, TST
ARB	3522	-1459	1/2" GOPH, DD 3542, FU 15' O:L,
LTD	3530	-1467	BAIL 4 GOPH, DD 3543 TD, NO
RTD	3532	-1469	INR IN FL, PB 3514, /3440-43,
DDTD	3540	-1477	A 2000, SWB LD & SWB 7 1/2 BOPH,
			/3420-24, PLUG @ 3430, /3403-
			06, A 1000, SWB LD & SWB 15
			BOPH, POP
			NO CORES

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS