

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24744-00-00  
Spot: S2SENESE Sec/Twnshp/Rge: 14-18S-23W  
1635 feet from S Section Line, 330 feet from E Section Line  
Lease Name: COOMBS Well #: 1-14  
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 221 N MAIN STE 300 PO BOX 2758  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204		

*144.63*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2008 5:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: DUSTY RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1590' WITH 50 SX CMT. 2ND PLUG AT 760' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 02/09/2008 7:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:


1ST PLUG AT 1590' WITH 50 SX CMT. 2ND PLUG AT 760' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 19 2008

CONSERVATION DIVISION  
WICHITA KS

INVOICED  
DATE 2-21-08  
INV. NO. 2008061268

Form CP-23  
*[Signature]*  
PKT