

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22110-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 18-28S-5W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: VINEY A Well #: 5  
County: KINGMAN Total Vertical Depth: 3950 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3932	2745	150 SX CMT.
SURF	8.625	318		250 SX CMT. <u>128.38</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2008 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM INC Phone: (316) 524-1225

Proposed Plugging Method: PER KCC RULES AND REGS

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/28/2008 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

ON 1/24/08 SET CIBP AT 3210' SPOTTED 4 SXS CEMENT ON TOP, SHOT OFF CASING AT 2745', PULLED CASING TO 877'. ON 1/25/08 SPOTTED 35 SXS CEMENT, PULLED CASING TO 461' PUMPED 150 SXS ~~25~~ CEMENT, LOST CIRUCLATION PULLED REST OF CASING, WENT BACK IN HOLE WITH BAILER ON SAND LINE TAGGED CEMENT AT 351'. ON 1/28/08 WENT BACK IN HOLE WITH 2 INCH POLY PIPE CIRCULATED FROM 351' TO SURFACE WITH 100 SXS OF CEMENT. TICKET #32679 COPELAND CEMENT CO.

INVOICED  
DATE 2/18/08  
INV. NO. 2008061216

Remarks: FLAT BOTTOM MILL STUCK IN HOLE AT ABOUT 3555' WITH 5 JOINTS OF TUBING ABOVE MILL.

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

B J Hope

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

FEB 11 2008

CONSERVATION DIVISION  
WICHITA, KS

PRT