

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19221-00-01
Spot: NWNENE Sec/Twnshp/Rge: 29-30S-7E
4920 feet from S Section Line, 1275 feet from E Section Line
Lease Name: STOLP Well #: 8
County: COWLEY Total Vertical Depth: 2910 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	2879		500 SX
PROD	7	2895		35 SX
SURF	10.75	90		70 SX

94.58

Well Type: EOR UIC Docket No: E17807.1 Date/Time to Plug: 12/31/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN DOR OIL COMPANY Phone: (620) 467-2615

Proposed Plugging Method: FILE BOTTOM OF HOLE W/SAND TO 50' ABOVE OPEN HOLE & DUMP BAIL 6 SXS CEMENT ON TOP, CIRCULATE CEMENT FROM 350'

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2008 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-31-2007, RIH W/TBG TO TAG BOTTOM PLUG, TBG STACKED OUT @ 2880', 15' FILL. LAYED TBG DOWN. SANDED BACK @ 2825', DUMP BAILED 6 SXS CEMENT ON TOP. 1-2-2008, RIH W/TBG @ 350', GEN-DOR MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1500 PM 1-2-2008. UNITED CEMENTING TICKET #8150.

Perfs:

Top	Bot	Thru	Comments
2895	2910		

INVOICED
DATE 2-18-08
INV. NO. 2008061217

Remarks: DOCKET #E-17,807, -096.67837,37.41666, OPEN HOLE 2895'-2910'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 11 2008

CONSERVATION DIVISION
WICHITA, KS

PKT