

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19281-00-00  
Spot: NENENE Sec/Twnshp/Rge: 29-30S-7E  
4891 feet from S Section Line, 539 feet from E Section Line  
Lease Name: STOLP Well #: 1  
County: COWLEY Total Vertical Depth: 2875 feet

Operator License No.: 9576  
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C  
Address: 8135 281ST RD  
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2872		35 SX CMT.
SURF	8.625	0		

93.44

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2007 8:00 AM  
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.  
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN-DOR OIL COMPANY Phone: (620) 467-2615

Proposed Plugging Method: FILL BOTTOM OF HOLE W/SAND TO 50' ABOVE PERFS DUMP BAIL 6 SXS CEMENT ON TOP. PULL PIPE, CIRCULATE CEMENT FROM 350'. RIH W/TBG TAG BOTTOM PLUG, PRODUCTION CASING HAS ALREADY BEEN PULLED.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2007 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-21-2007, RIH W/TBG TO TAG BOTTOM PLUG, TBG STACKED OUT @ 878'. HUNG UP INSIDE 5-1/2" CASING, WORKED LOOSE, LAID DOWN TUBING. SHUT DOWN. 12-26-2007 RIH W/TBG @ 970', TAGGED SOLID, COULD NOT GET BACK INTO CUT CSG. W/TBG @ 940', GEN-DOR MIXED & PUMPED 35 SXS CLASS A COMMON 2% GEL, FLUIDS CIRCULATED @ SURFACE DURING CEMENT JOB. PULLED TBG @ 350', GEN-DOR OIL CO. MIXED & PUMPED 165 SXS CLASS A COMMON 2% GEL. 12-27-2008. TAGGED TOP CEMENT PLUG @ 229'. RIH W/TBG @ 225', GEN-DOR OIL CO. MIXED & PUMPED 250 SXS 60/40 POZMIX 4% GEL. 12-28-2008, TAGGED TOP CEMENT PLUG @ 20', BAILED HOLE DRY 2 20', DRY DUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 1200 PM 12-28-2007. UNITED CEMENTING TICKET #S 8147, & 8153. 970' OF 5-1/2" CSG WAS PULLED FROM THIS WELL.

Perfs:

Top	Bot	Thru	Comments
2872	2875		


**INVOICED**  
DATE 2-18-08  
INV. NO. 2008061217

Remarks: -096.67808,37.41666, OPEN HOLE 2872'-2875'

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

FEB 11 2008

CONSERVATION DIVISION  
WICHITA, KS

