

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 207  
WICHITA, KANSAS 6720

API Well Number: 15-155-20679-00-00  
Spot: SESESW Sec/Twnshp/Rge: 36-26S-8W  
328 feet from S Section Line, 2974 feet from E Section Line  
Lease Name: MCCOLLOUGH Well #: 1  
County: RENO Total Vertical Depth 3700 feet

Operator License No.: 6139  
Op Name: BOYER, JAY C. ESTATE (DECEASED)  
Address: PO BOX 511  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3698		150 SX
SURF	8.625	216		115 SX

120.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2008 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: BILL SCHOENHOFER Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,480' & top with 4 sxs. cement. Rip 4 1/2" casing. Pull casing to 1,250' & spot 35 sxs. cement. Pull casing to 650' & spot 35 sxs. cement. Pull casing to 270' & circulate cement to the surface.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/30/2008 4:30 PM KCC Agent: MICHAEL WILSON

**Actual Plugging Report:**

Sanded to 3,480' & topped with 4 sxs. cement. Ran bailer & tagged bottom plug at 3,450'. Ripped 4 1/2" casing @ 2,132'. Pulled casing to 1,261' & spotted 35 sxs. cement with 50 lbs. hulls. Pulled casing to 652' & spotted 35 sxs. cement with 50 lbs. hulls. Pulled casing to 327' & circulated 110 sxs. cement to the surface.

**Perfs:**

Top	Bot	Thru	Comments
3624	3628	CSG	
3530	3534	CSG	

**INVOICED**

DATE 2-18-08

INV. NO. 2008061219

Remarks: USED 60/40 POSMIX W/4% GEL & 100 LBS. HULLS BY COPELAND ACID & CEMENT. INVOICE #33414.

Plugged through: CSG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

FEB 11 2008

CONSERVATION DIVISION  
WICHITA, KS