

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21040-00-00
Spot: NESW Sec/Twnshp/Rge: 23-2S-27W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: LONG TRUST 'A' Well #: 1-23
County: DECATUR Total Vertical Depth: 3770 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		

122.53

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/05/2008 5:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE Witness Type: NONE
Date/Time Plugging Completed: 02/05/2008 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug at 2239' w/25 sxs.
2nd. Plug at 1459' w/100 sxs.
3rd. Plug at 310' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 2-18-08
INV. NO. 2008061220

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 11 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

W

Signed

Bruce Rodie

(TECHNICIAN)

FEB 08 2008

PR