

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21494-00-00
Spot: NESW Sec/Twnshp/Rge: 20-32S-8W
1987 feet from S Section Line, 3384 feet from E Section Line
Lease Name: GILLA Well #: 2
County: HARPER Total Vertical Depth: 3828 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3828	2840	125 SX CMT
SURF	8.625	239		195 SX CMT
T1	2.375	3768		

124.47

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/30/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3680 AND CAP WITH 4 SKS OF CMT. RECOVER CASING. 35 SKS AT 1300', 35 SKS AT 750', CIRCULATE CMT FROM 300'-0'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/30/2008 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3680' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2840' AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 750', WHERE 35 SKS OD CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRC TO 0'.

Perfs:

Top	Bot	Thru	Comments
3720	3723		

INVOICED
DATE 2-18-08
INV. NO. 2008061222

Remarks: QUALITY OILWELL CEMENTING 60/40 POS 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

FEB 11 2008

CONSERVATION DIVISION
WICHITA, KS

Handwritten initials