

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-21138-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 9-26S-18E
1363 feet from S Section Line, 2055 feet from E Section Line
Lease Name: MONARCH Well #: 16
County: ALLEN Total Vertical Depth: 795 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO., A GENERAL P
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	775	0	
SURF	6	20	0	

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2008 12:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WAS AN OPEN HOLE COMPLETION WITH 2" CASING TO 775' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 01/21/2008 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700PSI. 30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

INVOICED
DATE 2-18-08
INV. NO. 2008061225

RECEIVED
KCC DISTRICT #3
JAN 30 2008 CPT
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 11 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: THE SPOT LOCATION FOR THIS WELL WAS ESTABLISHED VIA GPS AS 1363' NSL & 2055' WEL OF SECTION 9.

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PST