

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-185-12888-00-00  
 Spot: SEWNWE Sec/Twnshp/Rge: 22-22S-14W  
990 feet from N Section Line, 1680 feet from E Section Line  
 Lease Name: OSCAR WEST Well #: 504  
 County: STAFFORD Total Vertical Depth: 3655 feet

Operator License No.: 33809  
 Op Name: BELPORT OIL, INC.  
 Address: 1443 S NORFOLK AVE  
TULSA, OK 74120

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		973		
CIBP		3440		WITH 2 SX CMT
PROD	5.5	3619	0	WITH 100 SX CMT <u>118.79</u>
SURF	8.625	238		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/05/2008 9:30 AM  
 Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
 Proposal Rcvd. from: GEORGE DAVENPORT Company: BELPORT OIL INC. Phone: (918) 584-8989

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 02/05/2008 1:13 PM KCC Agent: RICHARD LACEY

**Actual Plugging Report:**

SET CIBP @ 3440' & 2 SX CMT. SET CIBP @ 973'. MULTIPLE HOLES IN CASING BELOW 980'. PERFORATED 5 1/2" @ 850'. RAN TBG TO 855'. PUMPED 275 SX CMT DOWN TBG. CIRCULATED CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS AND 5 1/2" CASING. PULLED TBG OUT. TOPPED OFF HOLE WITH 55 SX CMT.

**Perfs:**

Top	Bot	Thru	Comments
3619	3655	OH	
3582	3588		

**INVOICED**  
 DATE 2-19-08  
 INV. NO. 2008061231

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 FEB 13 2008  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED  
 FEB - 8 2008  
 KCC Dodge City

Signed

*Richard M. Lacey*

(TECHNICIAN)