

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00185-00-00
Spot: Q NWNWSE Sec/Twnshp/Rge: 31-31S-35W
2640 feet from N Section Line, 2640 feet from W Section Line
Lease Name: BROWNELL Well #: 2
County: STEVENS Total Vertical Depth: 2830 feet

Operator License No.: 5208

Op Name: EXXONMOBIL OIL CORP

Address: 14950 HEATHROW FORREST PKWY PO
HOUSTON, TX 77210 Box 4358

String	Size	Depth (ft)	Pulled (ft)	Comments
L1		2830		
PROD 7		2567	0	WITH 900 SX CMT <u>9/1.98</u>
SURF 10.75		597		WITH 400 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 01/23/2005 12:30 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN SCHOOLCRAFT

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: 40 SX CMT @ 1800'. HULLS, PILL @ 1200'. CHECK 7" STRETCH. 40 SX CMT AT 630'. 10 SX CMT AT 40'. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/23/2008 4:30 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

****RODS & TBG LEFT IN HOLE. 7" CASING CEMENTED TO SURFACE.**** PUMP MUD - 40 SX CMT - 200# HULLS AT 1800' THROUGH TBG. NO CIRCULATION. SPOT 400# HULLS AT 1200' THROUGH TBG. NO CIRCULATION. PULL TBG TO 800' & CIRCULATE HOLE WITH MUD. FULL CIRCULATION. PUMP 40 SX CMT AT 630'. PUMP 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
2563	2830		

INVOICED
DATE 2-19-08
INV. NO. 2008061237

RECEIVED
KANSAS CORPORATION COMMISSION


FEB 13 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

Form CP-23