

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00186-00-00
Spot: NENESW Sec/Twnshp/Rge: 32-31S-35W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BARNARD Well #: 1
County: STEVENS Total Vertical Depth: 2815 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------------|
| L1 | | 2815 | | SLOTTED LINER |
| PROD 7 | | 2512 | 0 | WITH 850 SX CMT 91.49 |
| SURF | 10.75 | 542 | | WITH 300 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/04/2008 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 1500' WITH 40 SX CMT. HULLS @ 1100". PLUG AT 570' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2008 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 40 SX CMT & 100# HULLS @ 1500'. NO CIRCULATION. **WELL HAS CSG LEAK. 2 3/8" TBG FISH @ 1500'. ** PUMP 350# HULLS IN 10 BBL MUD @ 1000'. PULL TO 650' & CIRCULATE WITH MUD. PLUG AT 570' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2499 | 2815 | | |

INVOICED
DATE 2-19-08
INV. NO. 2008061237

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED
FEB - 7 2008
KCC Dodge City

Signed

Ken Jehlik

(TECHNICIAN)

Form 17-27