

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00273-00-00
Spot: NE Sec/Twnshp/Rge: 10-32S-38W
3820 feet from S Section Line, 1297 feet from E Section Line
Lease Name: PONDER Well #: 1
County: STEVENS Total Vertical Depth: 2750 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comments
L1		2477		
PROD	8.625	2495	690	WITH 150 SX CMT 89.38
SURF	12.5	585		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/18/2008 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/21/2008 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT & 200# HULLS AT 2265'. HAD FILL UP AT 2330'. HOLE WOULD NOT CIRCULATE WITH MUD. SPOT 500# HULLS @ 1200'. HOLE CIRCULATED. CIRCULATE HOLE WITH MUD & HULLS AT 615' THROUGH TBG. FULL RETURNS. PUMP 75 SX CMT AT 615' THROUGH TBG. FULL RETURNS. RAN BOND LOG IN 8 5/8". GOOD CMT FROM 510' TO 95'. PUMP 25 SX CMT AT 30' THROUGH TBG. FULL RETURNS.

Perfs:


Top	Bot	Thru	Comments
2515	2740		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2008

Remarks: USED COMMON CEMENT BY SARGENT.

Plugged through: TBG

District: 01



Signed

Steve R. [Signature]
(TECHNICIAN)

PKT