

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-16675-00-00
Spot: NWNE Sec/Twnshp/Rge: 4-34S-14W
4668 feet from S Section Line, 2129 feet from E Section Line
Lease Name: WHEAT B Well #: 1
County: BARBER Total Vertical Depth: 4740 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		720		
CIBP		4231		WITH 2 SX CMT
PROD	4.5	4739	0	WITH 250 SX CMT 154.05
SURF	8.625	352		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/04/2008 10:00 AM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: CHUCK TONER Company: PPSI Phone: _____

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2008 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SHOT TBG OFF @ 4396'. SET CIBP @ 4231' & 2 SX CMT. SET CIBP @ 720'.
PERFORATED 4 1/2" @ 700'. PUMP DOWN 4 1/2" CIRCULATING UP 8 5/8" X 4 1/2"
WITH 250 SX CMT. DID NOT GET CMT TO SURFACE. RAN OUT OF CMT. WAITED
1 1/2 HOURS PUMPED ANOTHER 250 SX CMT. GOOD RETURNS. NO CMT. 2/5/08:
FOUND CMT TOP @ 100'. FILLED 8 5/8" X 4 1/2" & 4 1/2" WITH 75 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4620	4696		


RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 2-19-08
INV. NO. 2008061244

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)