

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00211-00-00
Spot: NENENE Sec/Twnshp/Rge: 13-31S-9W
4967 feet from S Section Line, 275 feet from E Section Line
Lease Name: GRABS A Well #: 1
County: HARPER Total Vertical Depth: 4446 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

144.50

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE THE PERFS AND CAP WITH 7 SKS. RECOVER CASING. 50 SKS AT 1450', 50 SKS AT 900', CIRC CMT

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/08/2008 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

THE PERFS WERE COVERED WITH SAND TO 4320' AND CAPPED WITH 7 SKS OF CMT. THE PIPE WAS RECOVERED FROM 1350' AND PULLED TO 1350' WHERE 50 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 50 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 310', WHERE CMT WAS CIRC TO SURFACE. THE REMAINING PIPE WAS PULLED AND THE CMT WAS TOPPED OFF.

INVOICED
DATE 2-19-08
INV. NO. 2008061247


RECEIVED
KANSAS CORPORATION COMMISSION
FEB 14 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

