

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21413-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 13-31S-9W  
893 feet from S Section Line, 1060 feet from E Section Line  
Lease Name: GRABS B Well #: 2  
County: HARPER Total Vertical Depth: 3049 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N LOGAN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3040		125 SX
SURF	8.625	255		200 SX
T1	2.375	2948		

99-09

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/06/2008 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND PERF BACK 50' ABOVE AND CAP WITH 4 SXS OF CMT. 35 SKS 1450', 35 SKS 900', CIRC CMT 305-0'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/06/2008 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK TO 2890', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2210', AND PULLED TO 1450, WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 305', WHERE CMT WAS CIRC TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
2946	2948		

INVOICED  
DATE 2-19-08  
INV. NO. 2008001347


RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 14 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY WELL CEMENTING 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

PLG