

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19197-00-00
Spot: NWNESE Sec/Twnshp/Rge: 18-18S-10W
2294 feet from S Section Line, 952 feet from E Section Line
Lease Name: MARILYN ZINK Well #: 1
County: RICE Total Vertical Depth: 3497 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3296	1700	KCC PKT
SURF	8.625	550		

113.65

Well Type: SWD UIC Docket No: D02678.0 Date/Time to Plug: 01/22/2008 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 01/22/2008 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3230' AND CAP WITH 5 SX'S CEMENT, CUT OFF CASING @ 1700' AND PULL TO 1250' AND PUMP 35 SXS CEMENT. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 600' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3360	3495		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 14 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 2-19-08
INV. NO. 2008061249

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-33559. USED 270 SX'S TOTAL.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKG