


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 15 Twp. 26S Rge. 2E (E) (W)
Location as "NE/CNW/SW" or footage from lines CS/2 S/2 NE
Lease Owner Shed Ford Carman Well Owner
Lease Name P. F. Lygrisse "A" ^{AWB} _{KCC}
Office Address 202 Tri-State Bldg., Tulsa, Okla. Well No. 8
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced November 25, 1955 19____
Plugging completed December 9, 1955 19____
Reason for abandonment of well or producing formation Not producing commercial quantities of oil

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Viola Depth to top 3187 Bottom 3189 Total Depth of Well 3189 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

FORMATION	CONTENT	FROM	TO	SIZE	CASING RECORD	
					PUT IN	PULLED OUT
				7"	3172	1650'
				133/8"	95	Cemented In

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand to 3070 ft. and dump 6 sacks cement at 3070 ft.
Mud to 165 ft.
Set 15 ft. rock bridge and dump 25 sacks cement at 150 ft.
Mud to 20 ft.
Set 8 sacks cement on 5 ft. rock bridge
Filled to surface

Name of Plugging Contractor Lawrence Matthews & Son
Address Box 422 El Dorado, Kansas
(If additional description is necessary, use BACK of this sheet)

STATE OF OKLAHOMA COUNTY OF TULSA, ss.
Ford Carman (Employer or owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ford Carman
202 Tri-State Building, Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 55

My commission expires Nov. 13, 1956

Julius J. Cabel
Notary Public.

PLUGGING
FILE SEC 15 T 26 R 2E
BOOK PAGE 2 LINE 36

RECEIVED
STATE CORPORATION COMMISSION
12/29/55
WICHITA, KANSAS

15-173-00818-00-00

SHELL-P. F. LYGRISSE "A" #8
C S/2 S/2 NE Section 15-26S-2E
Greenwich Field
Sedgwick County, Kansas

Casing Record

13-3/8" cem 95 with 135 sax
7" cem 3172 with 250 sax

- 0 - 91 surface
- 95 lime
- 96 shale
- 107 lime
- 117 shale
- 125 lime
- 455 shale & shells
- 535 broken lime
- 985 shale & shells
- 1036 shale
- 1050 lime
- 1230 shale
- 1570 shale & shells
- 1710 shale & lime
- 2245 shale & shells
- 2363 broken lime & shale
- 2370 lime
- 2390 shale & shells
- 2420 sand
- 2460 shale & shells
- 2595 lime
- 2655 lime, hard
- 2705 broken shale & shells
- 2720 shale
- 2770 lime
- 2865 shale & shells
- 2879 v.c. shale & little chert SLC
- 2881 shale & shells
- 2886 v.c. shale & lime
- 2890 v.c. shale
- 2895 chat, hard Top Mississippian 2888
- 2898 chat, soft
- 2974 chat
- 2995 lime & chat
- 3023 chat
- 3078 chat & lime
- 3126 lime Top Kinderhook 3126
- 3187 shale Top Viola 3187
- 3189 1/2 lime T.D.

PLUGGING
 SEC 15 T26R2E
 PAGE 2 LINE 26

Dukes

JUNE 20 1953
 SLEED
 CONSERVATION
 Wichita, K.