

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

SEDGWICK County, Sec. 15 Twp. 26 Rge. 2 (E) E (W)

Location as "NE/CNW/SW" or footage from lines N/2 SW

Lease Owner D. M. Shawver

Lease Name Lygrisse "B" Well No. 1

Office Address 817 Central Building

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-24-49 19

Application for plugging filed 10-11-54 19

Application for plugging approved 10-12-54 19


Plugging commenced 10-13-54 19

Plugging completed 10-17-54 19

Reason for abandonment of well or producing formation Unprofitable production.

If a producing well is abandoned, date of last production 9-21-54 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Miss. Chat Depth to top 2871 Bottom 2876' Total Depth of Well 2876' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Miss. Chat	Oil	2871	2876	8 5/8"	95'	
				4 1/2"	2871'	1100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with sand to 2860', dumped 4 sax of cement with dump bailer.  
Top of cement, 2825'. Filled with mud to 140', set rock bridge,  
dumped 20 sax of cement. Top of cement, 80'. Filled with mud  
to 20', set rock bridge, dumped 5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Co.

Address P. O. Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

D. M. SHAWVER (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. M. Shawver

817 CENTRAL BUILDING

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 1954

My commission expires Nov. 30 - 1957

Notary Public.

PLUGGING  
FILE DEC 15 20 25  
BOOK PAGE 20 LINE 8

RECEIVED  
NOV 13 1954  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-173-03465-00-00

DRILLING LOG

WELL NAME: Lygrisse B #1  
 OWNERS: D. M. Shawver & Wm. Graham Oil Co.  
 CONTRACTOR: Laura Jane Oil Co., Inc.  
 DATE COMM: 3-10-49  
 DATE COMP: 3-24-49

LOCATION: N/2 SW/4 15-26-2# E  
 Sedgwick County, Kansas

PRODUCTION:

CASING RECORD: 95' - 8 5/8" 75' 2 1/2"  
~~2871'~~ - 4 1/2"  
 2871' - w/ 75' 2 1/2"

FORMATION	TO
Surface Clay	58'
Shale & Lime	2170'
Lime	2225'
Shale & Lime	2250'
Shale & Shells	2442'
Lime	2585'
Lime & Shale	2610'
Shale & Shells	2780'
Shale & Lime	2835'
Shale & Shells	2871'
Chat	2875'

ROTARY TOTAL DEPTH  
 2876' - CT. Total Depth

I certify that the above is a true and correct copy of the log of the Lygrisse B-1 located in the N/2 SW/4 of Section 15, Township 26 S, Range 2 E, Sedgwick County, Kansas, to the best of my knowledge.

LAURA JANE OIL COMPANY, INC.

BY: *D. M. Shawver*

Sworn and subscribed to before me this 9th day of December, 1949.

NOTARY PUBLIC

**PLUGGING**  
 PAGE SEC 15 T 26 R 25  
 BOOK PAGE 20 LINE 1