


15-173-19040-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
900 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 15 Twp. 26 Rge. 2 (E) E (W)  
Location as "NE/CNW/SW" or footage from lines SW  
Lease Owner D. M. Shawver  
Lease Name Lygrisse "BW" Well No. 3  
Office Address 817 Central Building  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 11/22/49 19  
Application for plugging filed 10-11-54 19  
Application for plugging approved 10-12-54 19  
Plugging commenced 10-17-54 19  
Plugging completed 10-20-54 19  
Reason for abandonment of well or producing formation Unprofitable production.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 9-21-54 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Miss. ~~Chat~~ ~~lime~~ Chat Depth to top 2884' Bottom Total Depth of Well 2886' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Miss. <del>lime</del> Chat	Oil	2884'		8 5/8"	107	
				4 1/2"	2886'	400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with sand to 2865', dumped 4 sax of cement with dump bailer, top of cement, 2830'. Filled with mud to 130', set rock bridge, dumped 20 sax of cement, top of cement, 70'. Mud to 20', set rock bridge, dumped 5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J & M CASING PULLING COMPANY  
Address P. O. BOX 711, GREAT BEND, OKANSAS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
D. M. SHAWVER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. M. Shawver  
817 CENTRAL BUILDING  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 54

My commission expires Mar. 30 - 1957

Rosemary [Signature]  
Notary Public.

PLUGGING  
FILE SEC. 15 T. 26 R. 2E  
BOOK PAGE 70 LINE 7

RECEIVED  
STATE CORPORATION COMMISSION  
NOV - 3 1954  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLING LOG

15-173-19040-00-00

Location: SW/4 Sec. 15-26S-2E, Sedgwick County

WELL NAME: LYGRISSE 3-B  
 OWNERS : Wm. Justice, Wm. Graham & D. M. Shawver  
 CONTRACTOR: Laura Jane Oil Co., Inc.  
 DATE COMM: 11/15/49  
 DATE COMP: 11/22/49

PRODUCTION:

CASING RECORD: 8 5/8" 107' Cem. W/50 s  
~~8 1/2"~~ 2886' (on Bottom)  
 4 1/2" Cem. W/50 sx.

Formation	To
Surface	107
Line-shale	275
Line	290
Red Rock	320
Shale-shells	540
Line-shale	725
Shale-shells	1810
Shale-line	1890
Line shale	2180
Shale-shells	2225
Shale-line	2325
Shale	2430
Line	2585
Line shale	2862
Line	2886 TD Rotary
Conglomerate	2893
Chert hard	2894
Chert hard	2902 TD Cable
Chert	2901 C.T.P.

I certify that the above is a true and correct copy of the log of the Lygrisse 3-B located in the SW/4 of Section 15-26S-2E, Sedgwick County, Kansas, to the best of my knowledge.

LAURA JANE OIL CO., INC.

BY: D. M. Shawver

Sworn and subscribed to before me this 9th day of December, 1949,

NOTARY PUBLIC

My Comm. Expires: 6/28/52

**PLUGGING**  
 FILE SEC 15-26-2E  
 BOOK PAGE 20 LINE 7

RECEIVED  
 OIL CORPORATION COMMISSION  
 OIL FIELD DIVISION  
 Topeka, Kansas