


15-173-03813-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 15. Twp. 26 Rge. 2 (E).....(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW SW
Lease Owner Shawver & Graham, Inc
Lease Name Lygrisse "B" Well No. "2"
Office Address 204 North Market, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed April 30 19 49
Application for plugging filed May 3 19 49
Application for plugging approved May 19 49
Plugging commenced May 3, 1949 19 49
Plugging completed May 6, 1949 19 49
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilley
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	110	None
				4 1/2	3275	2608'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Rocked hole from 2950 to 2890'. Run 2 sacks of cement.
Mudded hole to 150'. Run 8 sacks of cement.
Mudded hole to top. Run 3 wacks of cement. Well Completed.

5/12/49
MAY 12 1949
STATE CORPORATION COMMISSION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Shawver & Graham, Inc.
Address 204 North Market
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) J. A. Gilliland
204 North Market, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of May, 19 49

Dorance K. Sturgess
Notary Public.

My commission expires 1-29-53

PLUGGING
FILE SEC 15 T 26 R 76
94 4V

LYGRISSE "B-2"

Location:	NE NW SW 15-26-2E Sedgwick County Kansas	Rotary- Commenced: 3-29-49 Completed: 4-15-49
Operator:	Shawver-Graham, Inc. 204 N. Market Wichita, Kansas	Spudder- Commenced: 4-22-49 Completed: 4-30-49
Casing Record:	110' 8 5/8" Surface Casing Cemented with 85 Sacks Regular Two Sacks Calcium-Chlorid 3290' 4 1/2" Casing Cemented with 125 Sacks Regular	

L O G

(Figures indicate bottom of formation)

Clay	40	Shale	3292
Clay-Shells	60	Sand	3317
Shells-Shale	110	Sand-Shale	3319
Lime-Shale	740	Sand T. D.	3323
Shale-Shells	1470		
Shale-Lime-Iron	2655		
Shale-Lime	2891		
Chat-	2919		
Chat-Chert	2950		
Lime-Chert	3090		
Lime-Shale	3195		
Top Viola	3239		
Lime	3243		
Simpson-Sand	3270		
Sand T. D.	3275		

RECEIVED
Conservation Div.
MAY 27 1949
STATE CORPORATION
COMMISSION
KANSAS

The undersigned, Shawver-Graham, Inc., hereby certified that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHAWVER-GRAHAM, INC.

By: D. Shawver
President

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BE IT REMEMBERED that on this 10th day of May 1949, before me the undersigned, a Notary Public duly commissioned in and for the county and state aforesaid, came DWIGHT M. SHAWVER, President of Shawver-Graham, Inc., a Kansas Corporation, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Dwight M. Shawver
Notary Public

My Commission Expires:
1-29-53

PLUGGING
FILE SEC 15 T 26 R 4E
BOOK PAGE 94 LINE 44