


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

SEDGWICK County. Sec. 15 Twp. 26 Rge. 2 (E) E (W)
Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner D. M. Shawver
Lease Name Lygrisse "A" Well No. 2
Office Address 817 Central Building
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed December 1, 1949 19
Application for plugging filed February 15 19 54
Application for plugging approved February 15 19 54
Plugging commenced February 22 19 54
Plugging completed February 24 19 54
Reason for abandonment of well or producing formation Unprofitable production.

If a producing well is abandoned, date of last production January 3 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Mississippi Chat Depth to top 2868 Bottom 2872 Total Depth of Well 2872 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi - oil		2868	2872	8 5/8"	105'	none
				5 1/2"	2869'	2553' 53"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 2872' to 2850'. Dumped 6 sax cement at 2850' with dump bailer. Top of cement 2802'. Filled with mud to 100', set 10' rock bridge, dumped 15 sax cement, top of cement, 50'. Filled with mud to 20', set rock bridge, dumped 5 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M CASING PULLING COMPANY P. O. Box 711, Great Bend, Kansas
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. M. Shawver (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. M. Shawver
817 Central Building
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February ~~February~~ March, 19 54

My commission expires July 19, 1956
Melvin Lendemann Notary Public.

24-7368-5 3-53-20M

Received
3/10/54

PLUGGING
FILE SEC 15 T 26 R 2E
BOOK PAGE 13 LINE 44

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock


Wichita, Kansas

15-173-03811-00-00

Company - WM. JUSTICE, D.M. SHAWVER, & WM. GRAHAM SEC. 15 T. 26 R. 2E
 Farm - Lygrisse "A" No. 2 OIL COMPANY NW SE NW

Total Depth. 2872
 Comm. 11-24-49 Comp. 12-1-49
 Shot or Treated.
 Contractor. Laura Jane Oil Co., Inc.
 Issued. 10-28-50

County. Sodgwick
 KANSAS



CASING:
 8 5/8" 105'
 5 1/2" 2869' 3' Off Bottom

Elevation. 1379

Production. 168 BOFD

Figures Indicate Bottom of Formations.

surface	125
lime & shale	260
lime	410
shale & lime	800
shale & sholls	1520
lime & shale	1700
broken lime	1770
shale & lime	2250
shale	2330
lime	2350
lime & shale	2370
lime	2530
lime & shale	2580
shale	2625
lime & shale	2868
chat, RTD	2872
cable tools	2872
Total depth,	
Tops: Scout	
Mississippi	2868

PLUGGING
 PRJ SEC 15 T 26 R 2E
 WOOK PAGE 13 LINE 44