

STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bittling Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
 when reporting plug-
 ging off formations.

Sedgwick County, Sec. **15** Twp. **26s** Rge. **2** (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines **C E 2w 2sw 1/4**

Lease Owner **William R. Justice**

Lease Name **Mason** Well No. **1**

Office Address **519 So Broadway Wichita Kansas.**

Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**

Date well completed..... 19.....

Application for plugging filed **April 4 1950.** 19.....

Application for plugging approved **" 4 1950** 19.....

Plugging commenced **April 7 1950** 19.....


Plugging completed **April 17 1950** 19.....

Reason for abandonment of well or producing formation.....

Void of Oil

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? **Yes**



Locate well correctly on above
 Section Plat

Name of Conservation Agent who supervised plugging of this well.....

Producing formation..... Depth to top **2921 ft** Bottom **2926 ft** Total Depth of Well **2926 ft** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2 In	2921'	2711'
				5/8 "	95'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

- Total Depth, 2926 Ft**
- 1 3 ft rock 2926 ft to 2923 ft.**
- 2 Dump 3 sacks cement, at 2923 ft.**
- 3. Mud to 125 ft.**
- 4, Set 10 ft rock bridge at 125 ft.**
- 5, Dump 12 Sacks cement on rock bridge.**
- 6. Mud to 10 ft.**
- 7. 3 Ft rock bridge at 10 ft.**
- 8. Dump 3 Sacks cement on rock bridge fill to surface.**

RECEIVED
 Conservation-Div.
 JUN 9 1950
 STATE CORPORATION
 COMMISSION
 KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **William R. Justice**
 Address **519 So Broadway Wichita Kansas.**

STATE OF **KANSAS**, COUNTY OF **SEDGWICK**, ss.

(employee of owner) or (~~Witness~~) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Lawrence W. Matthews Jr.*
 123 N. Denver, El Dorado, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this **9th** day of **June**, 19**50**

My commission expires **January 31, 1953**
Seward S. Kreider
 Notary Public.

PLUGGING
 FILE SEC **15T 26R 2E**
 BOOK PAGE **141 23**

15-173-19038-00-00

DRILLING LOG

WELL NAME: Mason #1
OWNERS: W. R. Justice
COM: 2/1/50
COMP: 2/9/50 Rotary
2/12/50 Cable

LOCATION: C E/2 W/2 SW/4, 15-268-2E,
Sedgwick County
CASING RECORD: 8 5/8 @ 95'
PRODUCTION: *RA*

5 1/2 = 2921 ft

Formation	To	Remarks
Surface	105	
Line	740	
Line-shale	850	
Shale shell	1530	
Shale-lime	2390	
Line	2412	
Line-shale	2438	
Line	2578	
Line-shale	2590	
Line 2635	2635	
Shale-lime	2920	
Chat	2926 TD	
Cable Tool Depth	2927	

I certify that the above is a true and correct copy of the log of the Mason #1, C E/2 W/2 SW/4, 15-268-2E, Sedgwick County, to the best of my knowledge.

LAURA JANE OIL CO., INC.,

BY: *H. D. Shawver*
H. D. Shawver

Sworn and subscribed to before me this 10th day of March, 1950.

Carol F. Liss
NOTARY PUBLIC

My Comm. Expires 6/28/52

15 26 26
146 23

RECORDED

MAY 25 1950

STATE OF KANSAS
COMMISSIONER OF REVENUE
KANSAS