

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER API #15-173-20085-00-01

LEASE NAME Lygrisse

WELL NUMBER #1-B (SWD)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 26S RGE. 2 (E) or (W) XXX

COUNTY Sedgwick

LEASE OPERATOR Stekoll Petroleum, Inc.

ADDRESS 1434 KSB Bldg., Wichita, Kansas 67202

PHONE# (316) 262-7123 OPERATORS LICENSE NO. 8965

Character of Well SWD

Date Well Completed

Plugging Commenced 6/27/86

Plugging Completed 7/17/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? ElDorado

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		-0-		8 5/8"	202'	-0-
Casing				5 1/2"	3320'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 3320 feet each set.

****See other side of this form****

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor United Cementing & Acid Co., Inc. License No.

Address P.O. Box 712, ElDorado, Kansas 67042

STATE OF Kansas COUNTY OF Sedgwick, ss.

Stekoll Petroleum, Inc., Ray Stekoll, Operator (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ray Stekoll President

(Address) 1434 KSB Bldg., Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 86

My Commission Expires: 10-18-87

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS
Notary Public

7/22/86
JUL 22 1986 Form CP-4
Revised 08-84

**Ran 3000' 2 7/8" tubing and spotted 50 sax cement thru tubing. Pulled tubing,
Ran 60 sax cement at 275' inside of 5 1/2" casing and cemented to top.
Ran 275' of 3/4" tubing inside of 5 1/2" casing and cemented with 140 sax to top.
Ran 273' of 3/4" tubing between 5 1/2" and 8 5/8" casing and cemented with 60 sax to top.
Ran 3/4" to 40' cemented to surface, filled 5 1/2" from approx 150' to surface.
Welded with steel plate over all casing.