

15-173-03823-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 4-32

LOCATION SW SW NE

SEC. 15 TWP. 26S RGE. 2E

Dry Hole        Abandoned Oil Well X Abandoned Gas Well       

I have this date completed supervision of plugging of:

Well No. 3-A Lease <sup>KCCZAP</sup> PE Lygrisse "A"

Operator Ford Carman Supply Co. Address 202 Tri-State Building  
Tulsa, Oklahoma

Field        County Sedgwick

Total Depth 3197 Feet.

Plugging Contractor Lawrence Matthews & Son

Plugging Contractor's License No. 27

Address 123 N. Denver Street, El Dorado, Kansas

(Describe briefly the manner in which the well was plugged)

Corrosion bridge set at 2900 feet.

Dumped 6 sacks cement on corrosion bridge.

Mudded hole to 165 feet. Dumped 35 sacks cement on

15 foot rock bridge at 150 feet. Mudded hole to

15 foot. Set 10 sacks of cement on 10 foot rock bridge.

Filled to surface.

Paul Dinkels  
District Conservation Agent

Date November 10, 1955

PLUGGING  
NOV 15 26 2E  
NOV 4 32

12/13/55