

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -173-00817-00-01 (of this well)

Operator's Full Name Wichita Iron Metals

Complete Address Box 13021 Wichita, Ks.

Lease Name ^{KCC2AP} P.F. Lygrisse "A" Well No. # 7

Location SW NE NE Sec. 15 Twp. 26 Rge. 2 (E) W

County Sedgwick Total Depth 3307'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor Kelso Csg. Pulling

Address Box 176, Chase, Ks. 67524 License No. # 683

Operation Completed: Hour 1:00 Day 16 Month 9 Year 1980

The Above well was plugged as follows:

13" csg. 84' 195 sx. cement. 7" csg. 3155' 200 sx. cement. 4 1/2" csg. 3280'
60 sx. cement. Shot & pulled 2660' Of 4 1/2" csg. Left 620' Of csg in hole.
Shot & pulled 7" csg. 2016', United Cementing pumped 3 sx. hulls,
10 sx. gel, 50 sx. cement. down 7" csg. at 1990', left 1139' 7" csg. in
Hole. 9/10/80. Ran 2" tub. 210', United Cementing pumped 3 sx. gel,
1 sx. hulls, pulled 30' tub. United pumped 178 sx. cement. to 4' below
surface. Pulled 2" tub.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9-26-80
INV. NO. 7888-E

Signed: Allen Thompson
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
9/19/80
SEP 19 1980

CONSERVATION DIVISION
Wichita, Kansas