

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-173-20,369-00-00 ^R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name DARRAH OIL CO.

Complete Address CANTON BUREAU LANE, GREAT BEND KS 67550

Lease Name LYGASSE Well No. #1

Location C W/2 SE/4 Sec. 15 Twp. 26 Rge. 2 (East) (~~West~~)

County Sedgwick Total Depth 3181

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor TOWANDA WELL SERVICE

Address TOWANDA, KS. License No. 533

Operation Completed: Hour: 5:00 PM Day: 4 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

5 1/2" casing - 3180 / 125 sacks lost tools in hole run Adis wire line tool to cut line, run rods to tools to loose lost everything in hole (1300' rods). Shot 5 1/2" at 1805' pull casing to 1755' & United cementing spotted 35 sacks cement. pulled casing to 206' spotted 110 sacks cement to surface. SUBTERRANEAN logging inc. Leon, ks shot service casing.

Amount of Surface Casing: 8 5/8 - 231 / 135 sacks 2 hulls 29 gal 3% CC

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Don Thompson
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 8-9-82
INV. NO. 2326-E