

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20214-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name H-30 Drilling, Incorporated.

Complete Address: 200 North Main, Wichita, Kansas.

Lease Name Jones Well No. 1

Location SW-SW-NE Sec. 10 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3955

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 4:30 PM Day 22 Month 4 Year 1969

The Above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section at 800'.

Circulated hole with heavy mud. Pulled DP to 1040' and displaced 100 Sx. cement thru
DP from 1040' to 715'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

APR 25 1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Deibel
Well Plugging Supervisor

INVOICED
DATE 4/28/69
INV. NO. 9658-11

4-25-69