

KANSAS

28
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1968
CONSERVATION DIVISION
Wichita, Kansas
08-19-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-065-20165-00-00

Operator's Full Name Three G Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name DeBoer Well No. 1

Location S/2-SW-NE, Sec. 36 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3610'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: H-30 Drilling, Incorporated,

Address: 200 North Main, Wichita, Kansas. License No. _____

Operation Completed: Hour 10:00AM Day 17 Month 8 Year 1968

The Above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 705'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru
DP from 900' to 580'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*
Well Plugging Supervisor

DATE 8/19/68
INV. NO. 8297-W