

*24*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

*15-065-20186-00-00*

*Rec'd - 12-11-68*

Operator's Full Name Three G Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name DeBoer Well No. 2

Location NE-SE-NW Sec. 36 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3600'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Dunne-Gardner Drilling Company, Incorporated,

Address: 300 Schweiter Building, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 11:00AM Day 9 Month 12th Year 1968

The Above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru DP  
from 900' to 575'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from 240' to  
165'. Pulled DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 12/11/68  
INV. NO. 8994-W

Signed: *N. S. Pichler*  
Well Plugging Supervisor