

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1972  
01-10-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20513-00-00

Operator's Full Name Kedco Corporation, National Oil Co., and B & B Drilling, Inc.,

Complete Address 816 Union Center, Wichita, Kansas.

Lease Name Buss Well No. 1

Location SE-SW-NW Sec. 36 Twp. 8 Rge. (E) (W) 22

County Graham Total Depth 3620'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor B & B Drilling, Incorporated,

Address 720 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour 9:30 PM Day 7 Month 1 Year 1972

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 110 Cu. Ft. cement  
thru DP from 875' to 550'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru  
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. F. Fickel  
Well Plugging Supervisor

INVOICED

DATE 1-13-72

INV. NO. 4977-W