

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20277-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1969  
CONSERVATION DIVISION  
Wichita, Kansas

11-20-69

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name Jones Well No. 1

Location CNW-SW Sec. 10 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3720'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.         

Operation Completed: Hour 9:30 AM Day 17 Month 11 Year 1969

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru  
DP from 975' to 650'. Pulled DP to 220' and displaced 20 Sx. cement thru DP from 220'  
to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 11/20/69

INV. NO. 882-W