

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20133-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas

4-1-68

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box # 797, Great Bend, Kansas.

Lease Name Hull Well No. 1

Location 150' W of CSE-SE Sec. 15 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3118

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 11:00 PM Day 26 Month 3 Year 1968

The Above well was plugged as follows:

231'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 930' and displaced 100 Sx. cement thru
DP from 930' to 610'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/1/68
INV. NO. 12502-11

Signed: A. G. Fuchs
Well Plugging Supervisor