

15-065-20519-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1972
10/2/72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Circle Oil Company, Incorporated,
Complete Address 500 Bitting Building, Wichita, Kansas.
Lease Name Keith Well No. 2
Location CW/2-NE Sec. 16 Twp. 8 Rge. (E) (W) 23
County Graham Total Depth 3725'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 11:15 AM Day 28 Month 9 Year 1972

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 185 Sx.
3724'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to 3690'. Only perforations shown from 3557' to 3567'.
Sanded well back to 3525' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2400') and squeezed well initially with 5 sacks hulls and 16 sacks gel and followed with 110 Cu. Ft. cement from 1000' to 675' then 10 sacks gel from 675' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure --200#. Final Shut-in pressure--100#. (Mudding and Cementing by Sun Oil Well Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. D. Dicks*
Well Plugging Supervisor

INVOICED
DATE 10-2-72
INV. NO. 6400-12