

15-065-20412-02-02

Form CP-3
Rev. 6-4-68

KANSAS

22
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas
2/8/71

Operator's Full Name Dane G. Hansen Trust,
Complete Address Logan, Kansas.
Lease Name Wilson Well No. K-3
Location NE-NE-SW Sec. 32 Twp. 8 Rge. (E) (W) 23
County Graham Total Depth 3940'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor C & G Drilling Company
Address 1107 Union National Bldg., Wichita, Ks. License No.
Operation Completed: Hour 5:30 AM Day 5 Month 2 Year 1971

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 925'.
Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 825'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 2/8/71
INV. NO. 3317-W