

15-065-02680-00-01

4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 20 Twp. 8 Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE/NW/NW

Lease Owner Leo J. Dreiling Oil Co.

Lease Name Higer Well No. A-3

Office Address Victoria, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging filed \_\_\_\_\_ Oct. 8, 19 64

Application for plugging approved \_\_\_\_\_ Oct. 12, 19 64

Plugging commenced \_\_\_\_\_ Oct. 24, 19 64

Plugging completed \_\_\_\_\_ Oct. 26, 19 64

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	151'	None
				5 1/2	3737'	2093'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3720' to 3670'. Mixed and dumped 5 sx. of cement from 3670' to 3640'. Pulled casing to 500'. Mixed and pumped in 5 sx. of gel mud. Would not circulate. Pulled casing to 440'. Mixed and pumped in 20 sx. of cement from 440' to 380'. Pulled casing to 260'. Mixed and circulated 5 sx. of gel mud. Pulled casing to 200'. Mixed and pumped in 20 sx. of cement from 200' to 140'. Pulled rest of casing. Bailed off gel to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1964

11/12/64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.

Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Ellis, ss.

Leo J. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo J. Dreiling

Victoria, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 64

My commission expires June 10, 1965

Notary Public.